

SECTION A-A

SCALE 1:50

ELECTRICAL LEGEND

	PLESSY ECONOMETER AND DISTRIBUTION BOARD 1700 mm AFFL
	CEILING LIGHT AS SPECIFIED
	50 WALL MOUNTED WATER TIGHT FITTING 2250mm ABOVE F.F.L
	DOUBLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL
	SINGLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. DOUBLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. SINGLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. DOUBLE WALL SOCKET AT 1200mm ABOVE FINISHED FLOOR LEVEL
	STOVE CONNECTION AT 1200mm ABOVE FINISHED FLOOR LEVEL
HWS	HOT WATER SYSTEM TO BE MOUNTED 2200mm A.F.F.L ON BATHROOM EXTERNAL WALL
T	TELEPHONE POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL
TV	TV. POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL
	1200mm SINGLE TUBE FLUORESCENT LIGHT FITTING

NATIONAL HOUSING ENTERPRISE
7 Omuramba Road, Eros P.O.Box 20192, Windhoek
Telephone (061) 2927111 Fax (061) 292 7270

ARCHITECTURAL TECHNICIAN
MANNETY MATONGO
CELL: 0811442420
P. O BOX 20192 EROS
WINDHOEK

OWNERS DETAILS

NATIONAL HOUSING ENTERPRISE
P O BOX 20192 WINDHOEK
TELL: 061 2927111

PROJECT TITLE:

HOUSE TYPE CORE 5 (110 WALL)
ON ERF 525 AIMABLAAGTE MARIENTAL

DRAWING TITLE:

SECTION
LAYOUT

COVERAGE

ERF AREA	
HOUSE	35.84 sqm
TOTAL UNBUILD AREA	35.84 sqm
COVERAGE %	

MUNICIPAL STAMP

APPROVED

BUILDING INP:

CEO:

I/WE HEREBY DECLARE THAT THE INFOMATION PRESENTED ON THIS DRAWING IS A TRUE REFLECTION OF THE SITE CONDITION, EXISTING BUILDING & MUNICIPAL SERVICES.

OWNER: (signature)

ARCH. TECHNICIAN: (signature)

NHE DIVISION:TECHNICAL SERVICES & PROPERTY MANAGEMENT.

CHECKED FOR CORRECNESS H BOCK HEAD DRAWING OFFICE	DATE	CHECKED FOR COMPLIANCE S. INDILENI ACT. MANAGER PROJECTS
	DATE 24/11/2023	APPROVED T. SHILONGO SENIOR EXECUTIVE TS & PM

DRAWING NO.	SCALE	DRAWING NO.
NHE-061231/2-07 B	AS SHOWN	2 OF 2