




CLAY FACEBRICK  
EXTERNAL WALL FACADE  
(200x100x75mm ) BRICK SIZE  
MORTAR JOINTS TO BE 10mm  
BETWEEN BRICKS BUILDING TECHNIQUE  
TO BE DONE ACC. TO ARCHITECTS  
DETAILS & SPECS.




WEST ELEVATION  
SCALE 1:100



SOUTH ELEVATION  
SCALE 1:100



EAST ELEVATION  
SCALE 1:100



NORTH ELEVATION  
SCALE 1:100

## ELECTRICAL LEGEND

	PLESSY ECONOMETER AND DISTRIBUTION BOARD 1700 mm AFEL
	CEILING LIGHT AS SPECIFIED
	50 WALL MOUNTED WATER TIGHT FITTING 2250mm ABOVE F.F.L
	DOUBLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL
	SINGLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. DOUBLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. SINGLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. DOUBLE WALL SOCKET AT 1200mm ABOVE FINISHED FLOOR LEVEL
	STONE CONNECTION AT 1200mm ABOVE FINISHED FLOOR LEVEL
	HOT WATER SYSTEM TO BE MOUNTED 2200mm A.F.F.L ON BATHROOM EXTERNAL WALL
	TELEPHONE POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL
	TV POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL
	1200mm SINGLE TUBE FLUORESCENT LIGHT FITTING



NATIONAL HOUSING ENTERPRISE  
7 Omuramba Road, Eros P.O.Box 20192, Windhoek  
Telephone (061) 2927111 Fax (061) 292 7270

## ARCHITECTURAL TECHNICIAN

MANNETY MATONGO  
CELL: 0811442420  
P. O BOX 20192 EROS  
WINDHOEK

## OWNERS DETAILS

NATIONAL HOUSING ENTERPRISE  
P O BOX 20192 WINDHOEK  
TELL: 061 2927111

## PROJECT TITLE:

HOUSE TYPE CORE 7 (110 WALL)  
ON ERF 537 AIMABLAAGTE MARIENTAL

## DRAWING TITLE:

SECTION & ELEVATION  
LAYOUT

## COVERAGE

ERF AREA	450 sqm
HOUSE	45,55 sqm
TOTAL UNBUILD AREA	47,55 sqm
COVERAGE %	10,56%

## MUNICIPAL STAMP

APPROVED	
BUILDING INP.	
CEO:	
I/WE HEREBY DECLARE THAT THE INFORMATION PRESENTED ON THIS DRAWING IS A TRUE REFLECTION OF THE SITE CONDITION, EXISTING BUILDING & MUNICIPAL SERVICES.	
OWNER: (signature)	
ARCH. TECHNICIAN: (signature)	
NHE DIVISION: TECHNICAL SERVICES & PROPERTY MANAGEMENT.	
CHECKED FOR CORRECTNESS H BOCK HEAD DRAWING OFFICE	DATE 24/11/2023
CHECKED FOR COMPLIANCE S INDIEN ACT. MANAGER PROJECTS	DATE 24/11/2023
SENIOR EXECUTIVE TS & PM	

DRAWING NO.	SCALE	DRAWING NO.
NHE-0612312-19 B	AS SHOWN	2 OF 2