





















SITE PLAN SCALE 1:200



DRAINAGE SECTION SCALE 1:200



ELECTRICAL LEGEND		
	PLESSY ECONOMETER AND DISTRIBUTION BOARD 1700 mm AFFL	
	CEILING LIGHT AS SPECIFIED	
	50 WALL MOUNTED WATER TIGHT FITTING 2250mm ABOVE F.F.L	
	DOUBLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL	
	SINGLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL	
	15 AMP. DOUBLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL	
	15 AMP. SINGLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL	
	15 AMP. DOUBLE WALL SOCKET AT 1200mm ABOVE FINISHED FLOOR LEVEL	
	STOVE CONNECTION AT 1200mm ABOVE FINISHED FLOOR LEVEL	
	HOT WATER SYSTEM TO BE MOUNTED 2200mm A.F.F.L ON BATHROOM EXTERNAL WALL	
	TELEPHONE POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL	
	TV. POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL	
	1200mm SINGLE TUBE FLUORESCENT LIGHT FITTING	
<div><p>NATIONAL HOUSING ENTERPRISE 7 Omuramba Road, Eros P.O.Box 20192, Windhoek Telephone (061) 2927111 Fax (061) 292 7270</p></div>		
ARCHITECTURAL TECHNICIAN MANNETY MATONGO CELL: 0811442420 P. O BOX 20192 EROS WINDHOEK		
OWNERS DETAILS NATIONAL HOUSING ENTERPRISE P O BOX 20192 WINDHOEK TELL: 061 2927111		
PROJECT TITLE: HOUSE TYPE CORE 5 (110 WALL) ON ERF 552 AIMABLAGTE MARIENTAL		
DRAWING TITLE: FLOOR,SITE & ELEVATION LAYOUT		
COVERAGE		
ERF AREA		434 sqm
HOUSE		35.84 sqm
TOTAL UNBUILD AREA		35.84 sqm
COVERAGE %		8,25%
MUNICIPAL STAMP		
APPROVED		
BUILDING INP:		
CEO:		
I/WE HEREBY DECLARE THAT THE INFORMATION PRESENTED ON THIS DRAWING IS A TRUE REFLECTION OF THE SITE CONDITION, EXISTING BUILDING & MUNICIPAL SERVICES.		
OWNER: (signature)		
ARCH. TECHNICIAN: (signature)		
NHE DIVISION: TECHNICAL SERVICES & PROPERTY MANAGEMENT.		
CHECKED FOR CORRECTNESS H BOCK HEAD DRAWING OFFICE	DATE 24/11/2023	CHECKED FOR COMPLIANCE S. INDILENI ACT. MANAGER PROJECTS APPROVED T. SHILONGO SENIOR EXECUTIVE TS & PM
DRAWING NO. NHE-061231/2-34 A	SCALE AS SHOWN	DRAWING NO. 1 OF 2