




CLAY FACEBRICK
EXTERNAL WALL FACADE
(200x100x75mm) BRICK SIZE
MORTAR JOINTS TO BE 10mm
BETWEEN BRICKS BUILDING TECHNIQUE
TO BE DONE ACC. TO ARCHITECTS
DETAILS & SPECS.




WEST ELEVATION
SCALE 1:100



SOUTH ELEVATION
SCALE 1:100



EAST ELEVATION
SCALE 1:100



NORTH ELEVATION
SCALE 1:100

ELECTRICAL LEGEND

	PLESSY ECONOMETER AND DISTRIBUTION BOARD 1700 mm AFEL
	CEILING LIGHT AS SPECIFIED
	50 WALL MOUNTED WATER TIGHT FITTING 2250mm ABOVE F.F.L
	DOUBLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL
	SINGLE LIGHT SWITCH AT 1400mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. DOUBLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. SINGLE WALL SOCKET AT 300mm ABOVE FINISHED FLOOR LEVEL
	15 AMP. DOUBLE WALL SOCKET AT 1200mm ABOVE FINISHED FLOOR LEVEL
	STOVE CONNECTION AT 1200mm ABOVE FINISHED FLOOR LEVEL
	HOT WATER SYSTEM TO BE MOUNTED 2200mm A.F.F.L ON BATHROOM EXTERNAL WALL
	TELEPHONE POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL
	TV POINT AT 300 mm ABOVE FINISHED FLOOR LEVEL
	1200mm SINGLE TUBE FLUORESCENT LIGHT FITTING



NATIONAL HOUSING ENTERPRISE
7 Omuramba Road, Eros P.O.Box 20192, Windhoek
Telephone (061) 2927111 Fax (061) 292 7270

ARCHITECTURAL TECHNICIAN

MANNETY MATONGO
CELL: 0811442420
P. O BOX 20192 EROS
WINDHOEK

OWNERS DETAILS

NATIONAL HOUSING ENTERPRISE
P O BOX 20192 WINDHOEK
TELL: 061 2927111

PROJECT TITLE:

HOUSE TYPE CORE 7 (110 WALL)
ON ERF 538 AIMABLAAGTE MARIENTAL

DRAWING TITLE:

SECTION & ELEVATION
LAYOUT

COVERAGE

ERF AREA	450 sqm
HOUSE	45,55 sqm
TOTAL UNBUILD AREA	47,55 sqm
COVERAGE %	10,56%

MUNICIPAL STAMP

APPROVED

BUILDING INP:

CEO:

I/WE HEREBY DECLARE THAT THE INFORMATION PRESENTED ON THIS DRAWING IS A TRUE REFLECTION OF THE SITE CONDITION, EXISTING BUILDING & MUNICIPAL SERVICES.

OWNER: (signature)

ARCH. TECHNICIAN: (signature)

NHE DIVISION: TECHNICAL SERVICES & PROPERTY MANAGEMENT.

CHECKED FOR CORRECTNESS H BOCK HEAD DRAWING OFFICE	DATE 24/11/2023	CHECKED FOR COMPLIANCE S. INDILENI ACT. MANAGER PROJECTS APPROVED T. SHILONGO SENIOR EXECUTIVE TS & PM
--	--------------------	---

DRAWING NO. NHE-061231/2-2018	SCALE AS SHOWN	DRAWING NO. 2 OF 2
----------------------------------	-------------------	-----------------------